

Gyrodatta Drilling Automation 2009



Manufacturer: Altro

Products: Altrogrip plus Two 1,700m²

Completion Time: 15 Days



Left: Stage 1 Floor Preparation using our own in-house HTC 800 Grinding Machine



Right: The Floor has been vacuumed, primed and in filled ready to receive the Epoxy Screed Finish



Left: The Altroflow EP is being hand applied using a steel trowel and finished with a spiked roller.



Right: The Altroflow is being scattered with Silica Sand to provide a non slip finish.

NIFL successfully installed 1,700m² of Altrogrip plus Two to Gyrodatta Drilling Automation, Barrow-in-Furness...

NIFL had to overcome many challenges during the installation including: moisture testing concrete in fills; identifying areas of oil contamination and working around other trades. Through the use of Altro's Surface Damp Proof Membrane and Oil Tolerant Primer along with good communication with the architect, NIFL overcame these challenges to produce an excellent finish.

FerFA Contractor of the Year 2006/2007
Nominated Specialists Awards 2009

NIFL Resin Flooring

Epoxy, Polyurethane and MMA Resin Flooring
Resin Bound and Resin Bonded Surfacing

t. 01482 856162

f. 01482 856168

Visit NIFL.co.uk!

NIFL
NIFL RESIN FLOORING